



## “Inverse Gas Lift System Installation in the UK North Sea”

---


Alun Whittaker – Geozone Technical Sales Manager

Neil Smith – Geozone Project Manager Well Services



# Presentation Outline

- Introduction
- Setting The Scene
- Solution – Inverse Gas Lift (IGLS)
- IGLS System Overview
- IGLS System Components
- IGLS System Variants
- Installation Procedure
- Lessons Learned
- Conclusion
- Questions




# Setting The Scene

## In General

- Numerous wells are now reaching the stage they require gas lift.
- Many of these wells were not designed to allow conventional gas lift.
- Annulus integrity may be compromised preventing gas injection.
- Gas Lift may be required below the production packer

## This Particular Installation

- Major UK Operator in the North Sea
- 5-1/2" Completion
- 4.562" Existing Safety Valve
- Liquid Loading Issues – Cyclic Flow
- A to B annulus integrity questionable
- Required Injection depth close to the reservoir




# Solution - Inverse Gas Lift - IGLS

What is IGLS ?


- IGLS allows a method of gas injection via an insert string.
- Gas injected through insert string – Coiled Tubing or Macaroni pipe.
- Production via annulus between insert string and existing production tubing.
- Installed Rigless in a live well using traditional intervention techniques.
- Utilises existing tree with new intermediate spool or Retrofit tree valve.
- Maintains fully functional master valves and SCSSSV.
- Fully retrievable for later in life abandonment
- NORSOK Compliant





# Renaissance – IGLS Overview




1. Intermediate Spool / Retrofit Valve c/w Concentric Hanger.
2. Intermediate IGLS Completion (Coiled Tubing or Jointed tubing)
3. Dual Flow Lock and Dual Flow Safety Valve
4. Coiled Tubing / Jointed Tubing Tail
5. Unloading Gas Lift Mandrel
6. Coiled Tubing / Jointed Tubing Tail
7. Gas Injection Valve




Upper Completion



Lower Completion



Lower Completion




## 5-1/2" x 4.562" IGLS Flow Areas

No	IGLS Component	Approx. length, ft	Equivalent Flow Diameter, in	Remarks
1	DFSV flow-by	1.5	1.846	13 x 0.512" diameter holes, flow area = 2.677 sq.-in
2	DFSV hanger centraliser	1.0	2.042	Flow area = 3.274 sq.-in
3	DFSV hanger top	0.3	1.996	Flow area = 3.130 sq.-in
4	Concentric hanger	1.7	2.064	9 x 0.688" diameter holes, flow area = 3.346 sq.-in

# IGLS Components - Intermediate Spool


- The one alteration required to the existing well for IGLS installation is at the wellhead, where an intermediate spool is inserted below the production tree.
- Internally, the spool has a profile to accept a concentric hanger, which separates the injection and production flow paths.






# IGLS Components – Spool & Concentric Hanger

- Intermediate Spool / Tree Valve Modification
  - Supplied by Weatherford or Xmas tree OEM.
  - No modification to existing Xmas tree required.
  - Application specific ID and length.




- Concentric Hanger

- No-go within intermediate spool.
- Lock-down or self locking.
- Gas injection and production paths.
- Run with standard industry tools.




# IGLS Components - Concentric Hanger Plug

- Concentric hanger plugs
  - BPV's
  - Barrier plugs
  - Flow through plugs



# IGLS Components – Seal Stinger

- Seal Stinger
  - Seals injection path between lower, intermediate and upper IGLS.
  - Stings into PBR on Suspension Hanger
  - Shear-able centraliser provides positive indication of space out.
  - Seal stinger c/w pump out plug, located into the safety valve lock PBR, connecting upper and lower sections.



# IGLS Components – Hangers

- Suspension Hanger
  - Carries full gas injection string weight, takes load off no-go by setting slips in the tubing ID above the existing Safety Valve
  - Gas injection through centre bore
  - Production via annular spaces and past slips.
  - Polished Bore Receptacle to sting into with upper IGLS.
- Dual Flow Hanger
  - Incorporates points above.
  - Carries full gas injection string weight, takes load off no-go by setting in the existing Safety Valve Nipple Profile – “retractable no-go” to remove string weight from no-go shoulder into lock profile.
  - Production via annular area throughout the hanger.




Suspension Hanger



Dual Flow Hanger


# IGLS Components – Dual Flow Safety Valve

- Insert valve that locates within existing safety valve seal bores.
- Controlled via existing SSV control line.
- Dual flow path, gas through centre & production through annular bore.
- Metal to metal seal on flapper & flow tube nose.
- Flapper closes off both injection & production paths.
- The DFSV is a rod piston activated safety valve with full API 14A 12<sup>TH</sup> Edition V4-1(Standard Service) & V4-2(debris & sand tolerant) ISO qualification. The key is the dual path, or concentric, flow tube that isolates the injection and production paths from each other.




# IGLS System Variants

- Upper section can be API Tubing or Coiled Tubing to surface.
- Split upper section, 2 stage or 3 stage module
- Addition of supplementary PBR and anchor latch stinger.
- Allows concentric hanger / stinger to be run as wireline module.
- Hanger can easily be pulled, allowing the well to be fully plugged with minimal effort, thus allowing topside work with full well control.



# System Variants – 3 Stage System



*Additional PBR and Anchor Latch tools in 3 stage IGLS completion.*

# Installation – Procedure / Technique


- Rigless Intervention
- Execution March / April 2018
- Multiple conveyance methods utilized during the Installation
- 2 x Well Control Barriers in place during the installation.
  - Deep Set Packer with Pump Out Sub set in Liner
  - Fluid column (well is sub-hydrostatic)
- Coiled Tubing
  - Lower IGLS Assembly was deployed using 2-3/8” Coiled Tubing as the tail and landed off in the Dual Flow Lock by the CT Injector head.
- Jointed Tubing
  - Intermediate IGLS Assembly was deployed using 2-3/8” FJ joint Tubing using the CT tower winch with a work basket and a false rotary table.
- Slickline
  - Upper IGLS Assembly deployed using Slickline to land the Concentric Hanger Landed off in the Intermediate Tubing Hanger Spool.






# Installation – Procedure / Technique

- Multiple Conveyance Methods - Coiled Tubing - 1
  - Lower IGLS Assembly Deployed using 2-3/8" Coiled Tubing as the tail and landed off in the CT BOP's once correct length had been run.



3 ft  
13.8 ft  
11 ft




Upper Work Window



- Standard CTU Rig Up
- Injector on top of CT Tower
- BOP Stack below weather deck

# Installation – Procedure / Technique



- Multiple Conveyance Methods - Jointed Tubing - 2
  - Lower IGLS assembly was landed off in the Dual Flow Hanger using the Coiled Tubing Injector and 2-3/8" FJ jointed Tubing with a work basket above the Injector head.



- Standard CTU Rig Up
- CT Injector inside CT Tower
- CT Gooseneck removed
- BOP Below weather deck
- Tubing was made up above the injector head using false rotary table.
- CT injector head used to deploy and land off the DHSV

# Installation – Procedure / Technique



- Multiple Conveyance Methods - Jointed Tubing - 2
  - Lower IGLS assembly was landed off in the Dual Flow Hanger using the Coiled Tubing Injector and 2-3/8" FJ jointed Tubing with a work basket above the Injector head.



- CT Tower winch used to deploy and land off Intermediate IGLS section
- Jointed Pipe BOP Stack below weather deck
- Tubing was made using false rotary table.

# Installation – Procedure / Technique

- Multiple Conveyance Methods – Slickline - 3
  - Upper IGLS Assembly Deployed using Slickline to land the Concentric Hanger in the Intermediate Tubing Hanger Spool.



- Slickline was rigged up inside of the CT Tower and used to deploy the upper section of the IGLS
- Upper section was landed off in the pre installed Concentric Hanger.

# Lessons Learned



1.  
S.I.T prior to going offshore. Land off, lock & pressure test Concentric Hanger in O.E.M spool piece.



2.  
Stack up test: Pull test connectors on Coiled Tubing – prove concept and equipment.



3.  
Workshop Integration checks between O.E.M and WFD Tools.

# Conclusion

- UK Installation
  - The IGLS system was deployed in an efficient and professional manner with no technical or safety concerns raised during the installation or operation.
  - “Inverse Gas Lift System” Eliminated a workover while increasing production to a well which had no gas lift capability nor annular integrity
  - Production up time was increased from 3 months per year to 12 months per year.
  - If platform ESD “trips” well can be taken back online immediately with no “down time”.
- Norway : Case History
  - Uplift on production from flowing a few days in a month to continuous flow, additionally, production rate has been doubled
  - Well moved from being a P&A candidate to an “online” producer
  - The full IGLS system was deployed using Coiled Tubing making it a Rigless intervention operation thus saving cost.



\* Under development



# OBJECTIVE is to ACHIEVE

INCREASED UPTIME

REDUCED COSTS

ENHANCED PRODUCTION

REDUCED FIELD PRESENCE

# Thank You & Questions

