



# Remote monitoring of a solids management system in the North Sea

Neil Meldrum  
Managing Director UK

Date 02/11/2022



# OUTLINE

---



PROJECT BACKGROUND

CYCLONE TECHNOLOGY RECAP

TECHNICAL & LOGISTICAL CHALLENGES

THE SOLUTION

RESULTS

# Project Background

---



A well, in the SNS, was shut-in due to clay and proppant production

Asset management wanted the 1,100 bbl/day well to be reinstated

A 7-week production clean-up was planned to reinstate the production while removing clay/proppant solids  
- while continuously monitoring the well performance

FourPhase was tasked with delivering a cyclonic DualFlow solids removal system

Normal DualFlow operation - 2 x crew day/2 x crew night operating the DualFlow offshore


SNS platform was a Normally Unmanned Installation (NUI)  
- the DualFlow was to be monitored from onshore, and a nearby control platform

Periodic visits by a FourPhase Supervisor to the NUI for DualFlow flushing and inspection

# Cyclone Technology Recap



Play Animation



# Technical & Logistical Challenges



# Remote monitoring of solids production on NUI

## Case study: Challenges

---

A NUI so no overnight crew support

Required a secure remote connectivity of the DualFlow to the control platform and onshore

Expected high solids production from the well which would require frequent solids flushing

Tight access to well bay laydown area

Limited crane capacity of 8tonnes – DualFlow semi-dismantled

Walk-to-Work vessel utilised during rig-up and commissioning phase

Only 12-hour daily operations window when crew shuttled offshore for vessel flushing/system inspection



# Equipment semi-dismantled

## Case study: Challenges



Removed one cyclone vessel of the DualFlow unit so under 8tonne crane capacity




Being loaded for road transport to customer port

# Access

## Case study: Challenges

Tight hatch entrance  
for lowering  
equipment down into  
the well bay 2.2m x  
2.2m



Reassembling  
DualFlow in a  
restricted space





# Identifying relative equipment dimensions/locations

## Case study: Challenges




Identifying laydown areas and calculating pipework lengths and routing

# Remote monitoring to shore

## Case study: Challenges



### Standard DualFlow HMI



Correct interfaces and protocols required to ensure a reliable and secure network to the control platform

# The Solution



# Feasibility study – Ensuring separation efficiency

## Case study: Solution



Basic well data was captured – flow rates, oil/gas properties, pressure, temperature, expected solids production, expected erosional rates etc.


A site visit was conducted to identify laydown areas, pipework routing, connections, utilities

Simulations were performed to ensure the planned operation was within the operating window of the DualFlow

The Feasibility Report captures all this information and becomes a central guiding document for the operation


# Planning using accurate 3D renders

## Case study: Solution



Creating a 3D rigup ensures an efficient rigup once offshore


Due to limited crane capacity the DualFlow installation was performed in two lifts then assembled/ disassembled despite tight well bay access



Using accurate measurements for equipment and piping ensured no excess material was shipped offshore – addressed ESG (Environment) metrics

# 3D simulation v Actual equipment location

## Case study: Solution




A 3D simulation allowed accurate equipment locations to be determined prior to rig-up operations

Actual DualFlow and Debris Tanks in position in wellbay

# Minimising POB

## Case study: Solution



Walk-to-Work vessel alongside during rig-up and initial flow back

Shuttling of FourPhase Supervisor for vessel flushing and system inspection

One Supervisor on stand-by onshore

Remote operator stations onshore in FourPhase's Bergen and Aberdeen facilities and remote access from the control room in the nearby control platform

# Remote monitoring


## Case study: Solution



The latest generation control system enables remote operation of all FourPhase equipment

An Industrial Personal Computer (IPC) runs a virtual Programmable Logic Controller (PLC) allowing a single IPC to operate all devices

A predictive maintenance program is supported through realtime data gathered from 500 soft & 60 hard sensors to optimise each clean-up operation





# Remote monitoring HMI


## Case study: Solution



The Human Machine Interface (HMI) was adapted to the customer specific interface including setting alarms – solids production, flow, differential pressure, air supply etc.

The DualFlow IPC integrates with the customer SCADA system

Remote access was granted to view a page of their SCADA system so the DualFlow could be monitored remotely. Cyber security protocols were followed to ensure read-only access




# Remote monitoring – Trending Screen

## Case study: Solution



Remote access to a trending view on the control platform SCADA permitted real-time observations of multiple data sets by the operations support team



- Wellhead P & T
- Weight of solids
- Inlet/outlet P
- Inlet/outlet T
- Diff Pressure#1
- Diff Pressure#2
- Choke v/v position
- Well flow rate
- Parallel/Series mode

# Case study: Results

Secured 1,000hrs of continuous production on an unmanned platform

Oil and gas production was kept at a higher rate because solids were continuously removed

Successful remote monitoring from multiple locations was achieved

By monitoring the DualFlow remotely, there was a significant reduction in personnel offshore costs and travel emissions

## Next steps

Continue developing remote monitoring and control capabilities

Now planning remote operations on several platforms

Integration of 3<sup>rd</sup> party systems into the FourPhase ecosystem will permit fully remotely operated production flow recovery



## Final thoughts

With an increasing number of marginal fields and NUIs offshore, innovative solutions are required for managing offshore energy production. Without personnel onboard, secure connectivity and data flow are the key drivers to achieving reliable and safe offshore operations.

Thank you

